

IIMU/Misc Work/2022-23/02  
**Indian Institute Of Management**  
**Udaipur**

Balicha,Udaipur  
Rajasthan - 313031

Dated: 8th Feb, 2023

**NOTICE INVITING QUOTATION**

Sealed quotations are inviting from Open market for "Miscellaneous work in the Academic block at IIMU".

The Estimated cost is amounting to **Rs 1,20,825/-** (Rupees One lakhs Twenty thousand eight hundred twenty five Only), including of all taxes. The hard copy of Schedule of Quantities can be downloaded from IIMU website "www.iimu.ac.in"

Sealed quotation duly signed may be submitted on or before 15.02.2023 till 11:00 AM and the same shall be opened on 16.02.2023 at 11:00 AM in the presence of quotationers or their authorized representative who like to be present.

The Institute reserves the right to accept or reject any/all quotations without assigning any reason whatsoever.

  
08/02/23  
**Ritesh Raj**  
**Assistant Manager- Estate**

(To be submitted on letter head)

<b>Name of work: Miscellaneous work in the Academic block at IIMU</b>					
<b>S.no</b>	<b>Item</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
1	Stone work(machine cut edges Veneer work)for wall lining upto 10 m height, backing filled with a grout of 12 mm thick cement mortar 1:3( 1 Cement : 3 coarse sand) and jointed with Cement mortar 1:2 (1 cement : 2 stone dust), including rubbing and polishing complete. (To be secured to the backing and the sides by means of cramps and pins which shall be paid separately). <b>25mm thick Blasted Mandana Stone</b>	sqm	10		
2	Providing and fixing dry cladding at all heights with <b>Mandana Stone 30mm</b> thick gang saw cut stone with (machine cut edges) of uniform colour and size upto 1mx1m, fixed to structural steel frame work and/ or with the help of cramps, pins etc. and sealing the joints with approved weather sealant as per Architectural drawing and direction of Engineer-in-charge. (The steel frame work, stainless steel cramps and pins etc. shall be paid for separately).	sqm	10		
3	Providing and fixing carbon steel galvanised (minimum coating 5 micron) dash fastener of 10 mm dia double threaded 6.8 grade (yield strength 480 N/mm <sup>2</sup> ), counter sunk head, comprising of 10 mm dia polyamide PA 6 grade sleeve <b>approved make</b> , including drilling of hole in frame , concrete/ masonry, etc. as per direction of Engineer-in-charge. <b>10 x 80 mm</b>	each	30		
4	Providing and fixing adjustable stainless steel cramps of <b>approved make</b> , required shape and size, adjustable with stainless steel nuts, bolts and washer (total weight not less than 260 gms), for dry stone cladding fixed on frame work at suitable location, including making necessary recesses in stone slab, drilling required holes etc complete as per direction of the Engineer-in-charge.	each	25		
5	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. <b>Hot finished welded type tubes</b>	kg	250		
5	Providing & Fixing of 6 Kg/ sq. cm PVC Pipe ISI marked brand as per IS 4985 self fit type complete. The work including solvent jointing hydraulic testing the joints & pipes as mentioned in the specification etc. making holes including chasing in solid block masonry walls with groove cutting machine to required width and depth, making holes in brick or RCC wall as per requirement ,clearing the debris, grouting of concealed pipes, making good the chase as mentioned, making good the wall and floors, making connection with down take to satisfaction of engr / arch with proper care, protecting fittings & pipes till the final handing over etc as directed by E-I-C complete as per specifications & drawing provided for all places, all heights & all levels (Concealed work for toilet block)				
5.1	110 mm dia OD	Metre	25		

6	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	Cum	5		
7	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all loads including all lifts involved	Cum	3		
			Taxable Value		
			Add:- CGST		
			Add:- SGST		
			<b>Total</b>		

## Terms and Conditions

1. The work shall be carried out as per CPWD specifications.
2. No T& P shall be issued by the institute.
3. The agency shall adhere to, and should follow Safety rules
4. Please note that the time is the essence of the contract. Time allowed for carrying out the work is 45 days.
5. You have to follow all the safety measures, in case of any happening due to any carelessness in safety regulations, IIMU will not be held responsible. No claim whatsoever will be entertained in this regard.
6. Electricity will be provided on chargeable basis as per IIMU norms.
7. Care shall be taken by the contractor during the execution of the work to avoid damage to the building. He shall be responsible for repairing such damages and restoring the same. He shall also remove all unwanted and waste materials arising out of the installation from the site of work from time to time.
8. The contractor shall dispatch materials to site in consultation with the Estate Officer. Suitable lockable storage accommodation shall be made available free of charge temporarily. However, watch and ward, shall be the responsibility of the contractor. Program of dispatch of material shall be framed keeping in view the progress of work. Safe custody of all machinery and equipment supplied by the contractor shall be the responsibility of the contractor till final taking over by the department.
9. The final inspection and checking will be done by the Estate Officer or his representative.
10. The scope of work:  
The work will be carried out in Academic Building, Hostels or in any buildings if required in the campus. The material shall be got approved from Estate Officer or his authorized representative before its use at site. The agency shall remove rejected material from site of work within three days of rejection, otherwise it will be got removed by institute themselves and the expenditure incurred will be recovered from your bill. In this regard no claim whatsoever will be entertained.
11. If the stipulated quantity of various items exceeds the BOQ quantities in this stipulated work up to three months of award of work, the agency will not be paid any variation in rates.
12. It will be the responsibility to submit computerized measurement & bill. Payment will be made after verification of measurement.
13. Rates agreed are inclusive of
  - Transportation, Loading-unloading at site.
  - Transit Insurance of material.
  - Scaffolding required up to three-meter height.
  - Testing and commissioning charges.
  - All the taxes, duties i/c.
14. The work shall be carried out in occupied campus; therefore, all care should be taken not to disturb the occupants.
15. You are requested to obtain contractor labour (Regulation & Eradication) license/EPFO, ESIC registration.
16. Owner reserves the right to increase or decrease the scope of work.
17. Extra Items-Nothing extra shall be paid for minor variations in the layout, design or specification. Any major alterations and changes certified by the Design consultant will be treated as extra item, the rate for which will be derived from relevant contract rate.
18. The Client may at any stage of work instruct the contractor to stop the work and obtain immediate clarification/further instructions from the Estate Officer. Any work done subsequent to such an instruction, without clarification, if later found unacceptable, shall have to be redone/rectified, entirely at the risk and cost of the contractor.
19. Termination of Contract-Owner/Estate Officer reserve the right to summarily terminate this contract either wholly or in part without payment or compensation to the contractor/ vendor other than that to which the contractor/ vendor may be entitled under the terms and conditions of this contract for work already executed by the contractor, if the contractor:
  - (a) Fails within Seven days' notice from Owner/Estate Officer to proceed diligently with commencement of the works to their satisfaction.

- (b) Refuse, delays or fails to rectify with similar notice, any defective workmanship and/or materials to Owner's / Estate Officer satisfaction.
- (c) Fails to complete and deliver up to the whole or any portion of the works, by the time or times specified or by such extended time or times as may be allowed by Owner /Estate Officer in writing.
- (d) Fails to withdraw immediately at Owner's /Estate Officer request any one or more of subcontractors, employees to whom Owner /Estate Officer objects or whose presence on the works contravene the conditions of this contract or may cause labour dispute in subcontractors or other trade and to replace such employees immediately by others against whom there is no such objection.
- (e) Makes any agreement with his creditors, have a receiving order made against the sub-contractor, execute bill of sale, or commit an act of bankruptcy or being a limited company, go into liquidation or have a receiver appointed or sublet the whole or part of this work without Owner's /Estate Officer written prior approval.
- (f) Fails within Three days' notice from Owner /Estate Officer to comply with any of the obligation of the sub-contractor herein contained.
- (g) The Client reserves the right to recover from the contractor's dues, cost of damages / losses incurred by the client due to such termination. The contractor / vendor shall not be entitled for any compensation of any kind, if the contract is terminated on account of any of the reasons stated above.
20. Timeline for Submission of rates of offline quotation is up to 10<sup>th</sup> February 2023 up to 11:00 Hrs. Quotation received after this will not be accepted and no claim whatsoever will be entertained.

Thanks,  
Ritesh Raj,  
Assistant Manager Estate  
IIM, Udaipur  
(+91-8789027271)